



**DATE:** August 29<sup>th</sup>, 2023  
**TO:** Area Media  
**FROM:** Mayor Rod Koch, City of South Sioux City  
**RE:** City of South Sioux City Street Improvements Plan

The City of South Sioux Council has approved a One & Six Year Plan at the August 29<sup>th</sup>, 2023 Council Meetings.

### **2023 - Completed Projects**

Ogden Court, from E 17<sup>th</sup> Street, south 775 feet. New 7" concrete paving, 31' in width. Project included water, sewer, drainage improvements, and fiber.

East 20<sup>th</sup> Street, from Dakota Avenue to A Street. Milling and 2" asphalt Overlay.

6<sup>th</sup> Avenue from West 10<sup>th</sup> Street to West 11<sup>th</sup> Street. Milling and 2" Asphalt overlay

Intersections on West 13<sup>th</sup> and Highway 77. Milling and 2" Asphalt overlay.

B Street from East 9<sup>th</sup> to East 13<sup>th</sup>. Milling and 2" asphalt overlay.

1<sup>st</sup> Avenue from Dakota Avenue to West 13<sup>th</sup> Street. Milling and 2" asphalt Overlay. Lake area on Elmway Avenue. Milling and 2" asphalt overlay.

Campground Roads. Milling and 2" asphalt overlay.

F Street from East 21<sup>st</sup> Street to East 22<sup>nd</sup> Street. Milling and asphalt overlay.

### **2024 - One Year Plan**

- #32 Random panel replacement  
Random storm drainage system repairs and replacement.
- #62(8) East 32<sup>nd</sup> Street from Dakota Avenue to the trail. Complete concrete or asphalt street improvement with water, sanitary sewer, and storm sewer improvements. \$850,000
- #67 C Street from East 21<sup>st</sup> Street to East 23<sup>rd</sup> Street. Milling and 3" asphalt overlay. Work shall include drainage structures. \$90,000
- #168 West 21<sup>st</sup> Street, connecting West 21<sup>st</sup> Street with Commerce way, west 750 feet. New 7" concrete paving, 31' in width. Project will include water lines, sanitary sewer lines, roadway fill, storm sewer and drainage improvements. \$660,000
- #169 Commerce Way, connecting Commerce Way with West 21<sup>st</sup> Street south 775 feet. New 7" concrete paving, 31 feet in width. Project will include water lines, sanitary sewer lines, roadway fill, storm sewer and drainage improvements. \$660,000
- #180 Roundhouse Road from end of existing paving south of West 29<sup>th</sup> Street, south to West 39<sup>th</sup> Street. New 7" concrete paving, 31 feet in width. Work shall include drainage improvements. \$700,000



- #182 West 39<sup>th</sup> Street and BNSF railroad crossing. Construct Quiet Zone Area at the railroad crossing per railroad standards and requirements. Work shall include pavement replacement, islands, signals, and signage. \$1,200,000
- #183 G Street and BNSF railroad crossing. Construct Quiet Zone Area at the railroad crossing per railroad standards and requirements. Work shall include pavement replacement, islands, signals, and signage. \$500,000
- #184 Hovey Development Phase III, new 7" concrete paving, 31' in width. This will connect from NE part of East 19<sup>th</sup> Street to Sampson and Hovey Lane. Project will include water, sewer, storm water, fiber, electric infrastructure and proper drainage on new street. \$900,000
- #185 East 11<sup>th</sup> Street, from B Street to G Street. Milling and 2" asphalt overlay. \$130,000
- #186 West 13<sup>th</sup> Street, from 1st Avenue to 5<sup>th</sup> Avenue. Milling and 2" asphalt overlay. \$100,000
- #187 East 12<sup>th</sup> Street, from F Street to G Street. Milling and 2" asphalt overlay. \$35,000
- #189 Colonial Drive, from Dakota Avenue to Wedgewood Drive. Milling and 2" asphalt overlay. \$50,000
- #190 Fairview Drive, from Colonial Drive to end of Fairview Drive. Milling and 2" asphalt overlay. \$50,000
- #191 Wedgewood Drive, from Dakota Avenue to C Street. Milling and 2" asphalt overlay. \$90,000
- #192 A Street, from Riverview Drive to East 7<sup>th</sup> Street. Milling and 2" asphalt overlay. \$20,000
- #193 East 8<sup>th</sup> Street, from Dakota Avenue to A Street. Milling and 2" asphalt overlay. \$20,000
- #194 East 26<sup>th</sup> Street, from Dakota Avenue to B Street. Milling and 2" asphalt overlay. \$55,000
- #195 B Street, from East 25<sup>th</sup> Street to East 28<sup>th</sup> Street. Milling and 2" asphalt overlay. \$65,000

## **2 – 6 YEAR Plan:**

### **2025 – 2029 Street Plan:**

- #66(AB) B Street from East 17<sup>th</sup> Street to East 25<sup>th</sup> Street, concrete street replacement. 6-inch concrete paving, 31 feet in width with drainage structures, utility adjustments, lighting, and sidewalks. \$1,300,000
- #66(CD) B Street from East 26<sup>th</sup> Street to East 34<sup>th</sup> Street, concrete street replacement. 6-inch concrete paving, 31 feet in width with drainage structures, utility adjustments, lighting, and sidewalks. \$1,300,000
- #67 C Street from East 21<sup>st</sup> Street to East 23<sup>rd</sup> Street. Milling and 3" asphalt overlay. Work will include drainage structures. \$90,000
- #92(B) East 6<sup>th</sup> Street from E Street to G Street. Replace with new 4 lane concrete street, 8-inch thick concrete, 48 feet in width. Work will also include drainage, utility adjustments, lighting, and sidewalks. \$800,000



- #104 East 24<sup>th</sup> Street from Dakota Avenue to B Street. Replace existing concrete with 8" concrete, 31' in width. Work will include drainage, utility adjustments, and sidewalks. \$800,000
- #106 Replace existing concrete street along Eldorado Way from Pine Street to the dead end on the north. Replace existing concrete street with new 6-inch concrete, 31 feet in width with drainage, sidewalks. \$360,000
- #109 West 24<sup>th</sup> Street from Dakota Avenue to 4<sup>th</sup> Avenue. Complete street replacement, 6-inch concrete, 31 feet in width, with drainage structures. \$500,000
- #110 West 25<sup>th</sup> Street from Dakota Avenue to 2<sup>nd</sup> Avenue. Replace existing concrete street with 6-inch concrete, 31 feet in width with drainage and sidewalks. \$320,000
- #122 Roth Drive from US 77 to D Avenue, widen to 3 lanes and upgrade US 77 entrance with medians and turn lanes. Concrete thickness 8-10 inches, 38-foot wide paving width. Work will include drainage, utility adjustments, and lighting. \$1,400,000
- #125 Foundry Road from Riverview Drive to G Street, new concrete paving. 6-inch concrete, 31 feet in width. Work will include drainage, utility adjustments, and lighting. \$1,200,000
- #128 G Street from East 33<sup>rd</sup> Street to Cardinal Lane, widen with center turn lane. 7-inch concrete, 48 feet in width, with drainage, right-of-way, utility adjustments, lighting, and sidewalks. \$2,100,000
- #137 West Side trail along West 21<sup>st</sup> Street from ½ block east of 3<sup>rd</sup> Avenue to 4<sup>th</sup> Avenue; along 4<sup>th</sup> Avenue from West 21<sup>st</sup> Street to West 19<sup>th</sup> Street; along West 19<sup>th</sup> Street from 4<sup>th</sup> Avenue to 9<sup>th</sup> Avenue; along 9<sup>th</sup> Avenue from West 19<sup>th</sup> Street to West 21<sup>st</sup> Street; then west to Highway No. 77. 10 foot wide, 6-inch concrete trail. \$490,000
- #142 1<sup>st</sup> Avenue from West 3<sup>rd</sup> Street to West 9<sup>th</sup> Street, replace concrete street with 6-inch concrete, 31 feet in width with drainage, utility adjustments, and sidewalks. \$1,600,000
- #144 East 15<sup>th</sup> Street from G Street to F Street, replace existing street. Project will include right-of-way, utility adjustments, drainage structures, sidewalks, and 6-inch thick, 31-foot wide paving. \$300,000
- #145(B) West 17<sup>th</sup> Street, from Dakota Avenue to 5<sup>th</sup> Avenue. New 6" concrete paving, 31 feet in width. Project will include right-of-way, drainage structures, utility adjustments, and sidewalks. \$260,000
- #149 East 31<sup>st</sup> Street from Dakota Avenue to B Street, replace concrete street with 6-inch concrete, 31 feet in width with drainage, utility adjustments, and sidewalks. \$170,000
- #150 2<sup>nd</sup> Avenue from West 32<sup>nd</sup> Street to Colonial Drive, construct new 6" concrete paving, 31 feet in width. Project will include drainage structures, right-of-way, utility adjustments, and sidewalks. \$300,000
- #151 East 14<sup>th</sup> Street, from B Street to E Street, concrete street replacement. Project is 6-inch concrete paving, 31 feet in width, including drainage structures, utility adjustments, and sidewalks. \$220,000



- #152 East 27<sup>th</sup> Street from B Street to C Street, replace concrete street. New 6-inch concrete, 31 feet in width with drainage, utility adjustments, lighting, and sidewalks. \$100,000
- #155 2<sup>nd</sup> Avenue from West 39<sup>th</sup> Street, north 620 feet. Construct new 6" concrete paving, 31' in width. Work will include drainage structures and sidewalks. \$190,000
- #161 East 25<sup>th</sup> Street from G Street to Veterans Drive. 8-inch concrete, 31 feet in width with drainage, right-of-way, lighting, and sidewalks. \$940,000
- #162(6) West 19<sup>th</sup> Street from 2<sup>nd</sup> Avenue to 3<sup>rd</sup> Avenue, replace concrete street, with 6- inch concrete, 31 feet wide with drainage and sidewalks. \$155,000
- #163 East 30<sup>th</sup> Street from A Street to B Street. New 6" concrete paving, 31' in width. Project will include drainage structures and sidewalks. \$130,000
- #170 West 29<sup>th</sup> Street (Old Hwy 20), extend concrete paving from Daniel's Lane to Lake Street. New 9" concrete paving, 43 feet in width. Project will include lighting, water lines, storm sewer and grading improvements. \$3,500,000